

Afforestation Management Plan

Forest/Block Name: Karens

Plan details.

Plan Date: 19/09/2024
Planned start date: 27/09/2024
Planned end date: 31/12/2024
Plan prepared by: Mark Byrnes

Property details

Land Owner:
Forest Owner (If different): James Roy
Block General Location: CDC
Block location Address: 73 Soper Road, Te Houka
Legal Description: Pt Sec 6 Blk XLIX, Secs 9-10, Pt Secs 7-8 Blk L, Sec 11, Pt Secs 5, 7, 9 Blk LV, Secs 1, 3, 5-8 and Pt Secs 9-10 Blk LVI, Secs 503R, 618R and Pt Sec 505R Clutha Survey District
Property OT: OT119/86

Block Location

Regional Council: ORC
District Council: CDC
Access Road/Nearest Road: 73 Soper Road, Te Houka

Consultant/Principal Contractor

Consultant Company Name: Venture Forestry Limited
Consultant individual name:
Phone Number:
Postal Address: 176 Puddle Alley Road, Mosgiel 9011
Email Address:

Activity

Afforestation to be undertaken manually using people and spades. Planting will be continuous contoured lines wherever possible.

Block/s sizes (as per supplied map)

Block: 24/1
Species: Pinus Radiata
Area(ha): 43

Block: 24/2
Species: Pinus Radiata
Area(ha): 15.3

Block: 24/3
Species: Pinus Radiata
Area(ha): 6.2

Block: 24/4
Species: Pinus Radiata
Area(ha): 3.8

Block: 24/5
Species: Pinus Radiata
Area(ha): 3.1

Block: 24/6
Species: Pinus Radiata
Area(ha): 2.9

Block: 24/7
Species: Pinus Radiata
Area(ha): 1.1

Block: 24/8
Species: Pinus Radiata
Area(ha): 1

Block: 24/9
Species: Pinus Radiata
Area(ha): 0.6

Block: 24/100.4
Species: Pinus Radiata
Area(ha): 3.1

Block: 24/11
Species: Pinus Radiata
Area(ha): 0.4

Map Contents

Computer freehold register, date, north arrow:	Yes
Property boundaries within 200m:	Yes
Afforestation/Replanting area boundary	Yes
Species to be afforested or replanted:	Yes
Year Afforestation/Replanting is to occur	Yes
The segmentation boundaries within afforestation or replanting areas required by the wilding tree risk guidelines to calculate a wilding tree risk calculator score:	Yes
Contour lines at less than or equal to 20m intervals:	Yes
Erosion susceptibility classification (map overlay):	Yes
Location of significant natural areas and vegetation clearance:	No
Features to be protected during operation (Archaeological areas etc):	No
Any water body or the coastal marine area, including—	Yes
(i) wetlands larger than 0.25 ha and lakes larger than 0.25 ha; and	
(ii) rivers to their perennial extent; and	
(iii) rivers where the bankfull channel width is 3 m or more; and	
(iv) any outstanding freshwater body	
or water body subject to a water conservation order; and	
(v) any setbacks from any identified water body or the coastal marine area:	
Registered drinking water supply and any drinking water sources for more than 25 people within 1 km downstream of the commercial forestry activity:	NA
Existing roads, tracks, river crossings:	Yes

Significant Natural Areas (SNA):

SNA's present within or adjacent to the Afforestation/Replanting area/s? No
If yes describe,

Is there any Indigenous vegetation present? Ye
If yes describe,

- How SNA/indigenous vegetation going to be protected? (include description of setbacks etc.)
 - Indigenous vegetation is scattered throughout the blocks, these areas will have a 5m setback from afforestation where applicable.
- Operational restrictions, including restrictions on afforestation or replanting, earthworks operations, or harvesting, as applicable, that will be used to ensure that no commercial forestry activity occurs within the significant natural area.
 - Setback off of the legal boundary along the Clutha River will

exceed any required setbacks of 10m from a SNA.

WATER QUALITY & SEDIMENT

River present in Afforestation/replanting Area? Yes
Bank Full Width? Less than 3m &
Greater than 3m

Description of waterway/wetland (tributary of?):

Tributaries of the Clutha River run through and or adjacent afforestation areas on this property.

The Clutha River boundaries Block 24/3.

Wetland present in block? Yes

If yes, describe (size & nature):

There are some small areas of wetlands within the afforestation areas, these are unlikely to meet the criteria set out under the NEC CF. These wetland type areas will have a 5m setback.

Risk of sediment and/or wood debris being mobilised downstream:

There has been no mechanical land preparation undertaken prior to afforestation. The land preparation has been intensive grazing and some spraying. This combined with the activity being afforestation, greatly reduces, if not totally eliminates the risk of sediment and/or woody debris being mobilized downstream.

Fish spawning indicated in block during the Planting/replanting: Yes

If yes, Indicated spawning species:

Fish spawning indicated for brown trout and Chioock Salmon in or adjacent to the blocks.

Fish spawning indicated in block during the Planting/replanting: Yes

If yes, Indicated spawning species:

1. Chinook Salmon
2. Trout

Spawning date range:

1. 1 April – 31 September
2. 15 May to 15 September

Indigenous species of funa:

Are threatened or at-risk species of indigenous fauna present? No

If yes, describe how these areas will be protected:

How has the land been prepared for afforestation/replanting?

Vegetation Burnt:	NA
Mechanical land preparation:	No
Intensive grazing:	Yes
Sprayed:	Yes
Other (describe):	NA

Risk of sediment and or slash being mobilised (site specific):

No mechanical land preparation has been undertaken on these blocks. There is no woody debris present that could be mobilised and no disturbance that would cause sediment to be mobilised on these sites

Proposed heavy rainfall contingency and response:

After the afforestation occurs, Venture Forestry will carry out 2 other site visits. This is for release spraying and survival surveys. Other than the two visits outlined above, the land owner is responsible for the site. If requested by the landowner Venture Forestry will carry out further site visits.

Specific triggers or thresholds for action:

If alerted by landowner, or an issue observed when on site as described above.

Description including maintenance, post work monitoring and corrective actions:

With the soil type (Yellow & Green), topography and lack of disturbance prior to afforestation, it is not expected that any maintenance or corrective measures will be required. If there are areas that require maintenance of corrective actions, this will be done as soon as practical after discovering, or being alerted to, the potential risk.

Description of monitoring erosion and sediment effects of afforestation/~~replanting~~:

A minimum of two visits will be carried out post planting, these being for release spraying and for a survival survey. If there are any issues, or potential issues, then these will be addressed as soon as practical after observing or being made aware.

Set Backs

5m minimum setbacks from all perennial waterways and wetlands (tributaries), these include areas with aquatic vegetation that do not show on maps supplied to contractors

10m setback from legal boundary along Clutha river edge

10m setbacks from legal property boundaries, except where adjacent to forested area.

5m setbacks from external stand fences

NES CF setbacks have been calculated by Venture staff on site and using aerial imagery. Setback will be managed on site during replanting by the silviculture contractor, these will also be audited by Venture Forestry staff carrying out quality control checks.

Wilding Trees

Wilding risk calculator score and calculation sheet provided to council? Yes

Description of how wilding risk was calculated:

Wilding risk assessments were made with observations during site visits by Venture Forestry staff. There has also been consultation with the landowner/manager regarding predominant wind direction and grazing in and around these areas.

Description of:

- Any adjacent properties under the same ownership.
 - Refer to supplied map.
- Schedule for undertaking wilding inspections.

A minimum of two visits will be carried out post planting, these being for release spraying and for a survival survey. If there are wilding trees observed at these visits they will be addressed as soon as practical after observing or being made aware of by the owner.
- How wildings will be removed.

If wilding trees are required to be removed, this will be carried out by hand pulling, or cutting off and ground level and applying poison directly to the stumps.

Indigenous Birds

Procedures for Indigenous birds nesting in block:

Crew to stop work and alert Venture Forestry upon discovery of any indigenous birds nesting within block. Consultation with Parker Conservation as to the best course of action to cause least disturbance to the nesting birds. Harvest in the effected are will not continue until cleared by Parker Conservation or a suitably qualified person deems it no risk to do so.

Nesting is unlikely during the planting season as it is in the winter months.

No indigenous birds sighted at site visits prior to operation.

Plan Amendment made: NA

Date plan amended: Enter

Plan amended by:

Amended plan sent to Regional Council: NA

Amended plan sent to District Council: NA